

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-01915-00-00  
Spot: S2SW Sec/Twnshp/Rge: 31-17S-10W  
660 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: GEMEINHARDT Well #: 3-B  
County: ELLSWORTH Total Vertical Depth: 3266 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

PROD Size: 7 feet: 3262 60 SX CMT  
SURF Size: 15 feet: 120

15  
#106

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/11/2005 8:15 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Run tubing to top of Arbuckle and pump 25 sxs cement; perforate @ 1275'; 925' & 250'; run tubing to 1275' & pump 50 sxs  
Plugging cement; pull tubing to 925' and pump 50 sxs cement; and pull tubing to 250' & circulate to surface.  
Method:

RECEIVED  
KCC DISTRICT #2

JAN 14 2005

WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/11/2005 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Ran tubing to top of Arbuckle and pumped 25 sacks of cement. Perforated at 1275', 925', and 250'. Ran tubing to 1275' and pumped 50 sacks cement. Pulled tubing to 925' and pumped 50 sacks cement. Pulled tubing to 250' and circulated to surface.

60/40 posmix with 4% gel.

235 total sacks

Swift Services #7629

RECEIVED  
JAN 28 2005  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

DATE 1-28-05

\*INV. NO. 2005061116