

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22278-00-00
Spot: SENW Sec/Twnshp/Rge: 33-13S-21W
3190 feet from S Section Line, 3400 feet from E Section Line
Lease Name: SHERFICK B Well #: 1-33
County: TREGO Total Vertical Depth: 4108 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

SURF Size: 8.625 feet: 212

4133⁵¹

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/23/2005 8:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered out 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
Anhy 1695' - 1740'.
RTD 4108.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 01/23/2005 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st. Plug at 4050' w/25 sxs.
2nd. Plug at 1720' w/25 sxs.
3rd. Plug at 890' w/100 sxs.
4th. Plug at 262' w/40 sxs.
5th. Plug at 40' w/10 sxs - 8 5/8" wiper plug.

RECEIVED
JAN 26 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 1-28-05

INV. NO. 2005061120

JAN 24 2005