

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21274-00-01
Spot: SENW Sec/Twnshp/Rge: 23-34S-9W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease Name: LEWIS J Well #: 1-23
County: HARPER Total Vertical Depth: 5040 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

PROD Size: 4.5 feet: 5002 200 SX CMT
SURF Size: 8.625 feet: 308 UNKNOWN

1163⁸⁰

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/17/2005 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed
Plugging
Method:

Perfs 4599'-4604' & 4622'-4628'; sand to 4436'; 1500' & 35 sxs; 650' & 35 sxs; and circ 350'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 01/17/2005 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand to 4436' and capped with 4 sacks of cement. Recovered casing from 3110'. Pulled casing to 1500' and spotted 35 sacks of cement. Pulled casing to 650' and spotted 35 sacks of cement. Pulled casing to 350' and circulated cement to surface.

Allied Cement
60/40 with 4% gel

RECEIVED
JAN 28 2005
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
4622	4628		
4599	4604		


RECEIVED
KCC DISTRICT #2
JAN 20 2005
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

INVOICED
DATE 1-28-05
INV. NO. 2005061125