

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20502-00-00
Spot: NWNESESW Sec/Twnshp/Rge: 35-19S-1W
1150 feet from S Section Line, 3129 feet from E Section Line
Lease Name: ELWOOD / KOEHN E M Well #: 1
County: MCPHERSON Total Vertical Depth: 2990 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

PROD Size: 4.5 feet: 2989
SURF Size: 8.625 feet: 128

97'18"

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/19/2004 9:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: ALAN DEGOOD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: Sand to 2,835' & top with 4 sxs. cement. Shoot casing off & pull same. Run tubing to 425' & spot 35 sxs. cement. Pull tubing to 250' & circulate cement to the surface.

RECEIVED
KCC DISTRICT #2

JAN 13 2005

WICHITA, KS

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 11/19/2004 1:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2,820' & topped with 4 sxs. cement. Shot casing off @1,472' & pulled same. Ran tubing to 438' & spotted 2 yards slurry mix (50 sxs. cement). Pulled tubing to 258' & circulated 7 yards slurry mix (175 sxs. cement) to the surface.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2895 | 2915 | | |

RECEIVED
JAN 28 2005
KCC WICHITA

Remarks: USED SLURRY MIX BY HESSTON CONCRETE INC. INVOICE # 76852.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

DATE 1-28-05
200506115