

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21918-00-00
Spot: SESWSW Sec/Twnshp/Rge: 20-29S-6W
330 feet from S Section Line, 1050 feet from W Section Line
Lease Name: SOWERS Well #: 1-20
County: KINGMAN Total Vertical Depth: 4245 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

PROD Size: 4.5 feet: 4244 110 SX CMT
SURF Size: 8.625 feet: 263 225 SX CMT

4137.96

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/18/2005 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Perfs 4132'-4156'; sand 4080' & 4 sxs; 1100' & 35 sxs; 600' & 35 sxs; and circ 315'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 01/18/2005 12:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand to 4080' and capped with 4 sacks of cement. Recovered casing from 3620'. Pulled casing to 1100' and spotted with 35 sacks of cement. Pulled casing to 600' and spotted with 35 sacks of cement. Pulled casing to 315' and circulated cement to surface.

Allied Cement
60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
4132	4156		
RECEIVED KCC DISTRICT #2 JAN 20 2005 WICHITA, KS			

RECEIVED
JAN 28 2005
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED
DATE 1-28-05
INV. NO. 2005061126