

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20728-00-00
Spot: NWSESE Sec/Twnshp/Rge: 22-19S-1W
946 feet from S Section Line, 1039 feet from E Section Line
Lease Name: H D UNRUH Well #: B-1
County: MCPHERSON Total Vertical Depth: 2964 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

PROD Size: 4.5 feet: 2963 40 SX CMT
SURF Size: 8.625 feet: 185 100 SX CMT

33
#96

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/10/2004 10:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: ALAN L DEGOOD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: Sand to 2,920' & top with 4 sxs. cement. Rip casing loose & pull same. Run tubing to 425' & spot 35 sxs. cement. Pull tubing to 250' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 12/10/2004 2:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2,855' & topped with 4 sxs. cement. Ripped casing loose @ 1,250' & pulled same. Ran tubing to 438' & spotted 2 yards slurry mix (50 sxs. cement). Pulled tubing to 250' & circulated 7 yards slurry mix (175 sxs. cement) to the surface.

Perfs:

Top	Bot	Thru	Comments
2920	2945		

RECEIVED
KCC DISTRICT #2
JAN 21 2005
RECEIVED
WICHITA, KS
JAN 28 2005
KCC WICHITA

Remarks: USED SLURRY MIX BY HESSTON CONCRETE INC. INVOICE #77099.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED
DATE 1-28-05
INV. NO. 2005061115