

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-06456-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 5-18S-10W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HABIGER Well #: 1
County: RICE Total Vertical Depth: 3216 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

L1 Size: 5.5 feet: 3003 2625' to 3003'
L2 Size: 4.5 feet: 3215 2901' to 3215'
PROD Size: 7 feet: 2944
SURF Size: 13 feet: 530

#104⁵²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/12/2005 5:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Perf as far down in 4-1/2" liner as possible; put 10 sxs; perf @ 1250' 900' & 580'; run tubing to 1250'; pump 80 sxs; pull tubing to 900'; pump 80 sxs; pull tubing to 580'; and circ to surf.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 01/12/2005 5:30 PM KCC Agent: VIRGIL CLOTHIER

RECEIVED
KCC DISTRICT #2
JAN 19 2005
WICHITA, KS

Actual Plugging Report:

Perforated at 3210', 1250', 900', and 580'. Ran tubing to 3210' and pumped 10 sacks of cement. Pulled tubing to 1250' and pumped 80 sacks of cement. Pulled tubing to 900' and pumped 80 sacks of cement. Pulled tubing to 580' and circulated cement to surface. Pumped cotton hulls throughout plugging operation.

60/40 posmix with 4% gel.
Swift Services ticket #7632
Log Tech ticket #13784

Perfs:

RECEIVED
FEB 08 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 2-8-05
INV. NO. 2005061160