

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-01982-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 32-18S-9W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: VOLKLAND Well #: 2  
County: RICE Total Vertical Depth: 3241 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

PROD Size: 5.5 feet: 3233  
SURF Size: 8.625 feet: 313

#105<sup>33</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/13/2005 2:30 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Run tubing to top of Arbuckle; pump 50 sxs; perf @ 1100', 900' & 365'. Run tubing to 1100'; pump 35 sxs; pull tubing to 900'; pump 35 sxs; pull tubing to 365'; and circ surf.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/14/2005 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Ran tubing to top of Arbuckle and pumped 50 sacks of cement. Perforated at 1100', 900', and 365'. Ran tubing to 1100' and pumped 35 sacks of cement. Pulled tubing to 900' and pumped 35 sacks of cement. Pulled tubing to 365' and attempted circulation -- didn't get any.

On 1-14-2005 came and tagged cement top at 2362'. Ran tubing to 1100' to begin pumping 35 sacks of cement with cotton hulls. Pulled to 900' and pumped 35 sacks of cement. Pulled to 365' and got circulation.

60/40 posmix with 4% gel

Swift Services ticket #7634

Log Tech ticket #13785

Start time cementing on 1-14-2005 was 2:00 pm -- 405 sacks total

Perfs:

Top	Bot	Thru	Comments
3233	3241		<b>RECEIVED KCC DISTRICT #2 JAN 20 2005 WICHITA, KS  RECEIVED FEB 08 2005 KCC WICHITA</b>

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

**INVOICED**

DATE 2-8-05  
FILE NO. 2005061160