

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21777-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 1-21S-7W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BROTHERS Well #: 7-1
County: RICE Total Vertical Depth: 3610 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3608 175 SX CMT
SURF Size: 8.625 feet: 218 200 SX CMT

#117 33

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2005 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Sand perfs to 3450' and put 5 sxs cement on top; cut off 5-1/2" casing; pull to 1050' and pump 35 sxs; pull casing to 650' and
Plugging pump 35 sxs; pull casing to 270'; and circ cement to surface.
Method:

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 01/21/2005 1:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3450' and put 5 sacks of cement on top. Cut off 5-1/2" casing at 2550'.
Pulled to 1050' and pumped 35 sacks of cement. Pulled to 650' and pumped 35 sacks of
cement. Pulled to 270' and circulated cement to surface.

Copeland Cement #24950
60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3520	3524		
3499	3503		

RECEIVED
KCC DISTRICT #2

JAN 26 2005

WICHITA, KS

RECEIVED
FEB 08 2005
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 2-8-05
INV. NO. 2005061161