

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20324-00-00  
Spot: E2NWSE Sec/Twnshp/Rge: 4-17S-8W  
2055 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: KOHR Well #: 1  
County: ELLSWORTH Total Vertical Depth: 2920 feet

Operator License No.: 32302  
Op Name: KEY GAS CORP.  
Address: 155 N. MARKET - SUITE 900  
WICHITA, KS 67202

PROD Size: 5.5 feet: 1590 150 sxs cement  
SURF Size: 8.625 feet: 386 225 sxs cement

*\$9490*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/11/2005 11:30 AM  
Plug Co. License No.: 33436 Plug Co. Name: FORREST ENERGY LIMITED LIABILITY CO  
Proposal Rcvd. from: MIKE MCNAUL Company: KEY GAS CORP. Phone: (316) 265-2270

Proposed Plugging Method: Run tubing to 1250' and pump 40 sxs; perforate @ 435' and run tubing to 435'; and circulate cement to surface.  
Estimated top of cement outside of 5-1/2" to 690'.  
RECEIVED  
KCC DISTRICT #2  
JAN 14 2005  
WICHITA, KS

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/11/2005 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Pulled tubing out of hole. Ran tubing back down to 1250' and pumped 40 sacks of cement.  
Perforated at 435'. Ran tubing to 435' and circulated cement to surface.  
210 sacks of cement total  
60/40 posmix with 4% gel.  
Copeland Cement #25258

Perfs:

Top	Bot	Thru	Comments
1346	1352		
1333	1343		

RECEIVED  
JAN 28 2005  
KCC WICHITA

Remarks: PREVIOUSLY THE ANDREWS #1

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 1-28-05  
INV. NO. 2005061122