

3 120315

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 7644Operator: BOBBY E. MILLERName & 2061 INDEPENDENCE RD.Address SEDAN, KS 67361AB oil well X Gas Well SWD Well/ Input Well Other well as hereinafter indicated: Plugging Contractor: ELMORES, INC.Lic. # 32884Address: P. O. BOX 277, SEDAN, KS 67361Company to plug at: Hour: Day: 13 Month: 12 2004Plugging proposal received from: JOHN ELMORECompany Name: ELMORES, INC. Phone: 316-725-5744Were: TO PUMP CEMENT & GEL DOWN 7" CASING FOR BOTTOM & TOP PLUGS.

RECEIVED

JAN 28 2005

KCC WICHITA

Plugging Proposal Received by:

RON ROWEPlugging attended by Agent: All Part X

TECHNICIAN

None Operations Completed: Hour: Day: 15 Month: 12 2004

Actual Plugging Report: RAN 1" HYDRIL INSIDE 7" CASING TO 1100' & GELLED HOLE. PUMPED
30 SACKS CEMENT @ 1100'. PULLED 1" OUT. PERFORATED 7" @ 350'. RAN 1" BACK IN TO 350' AND
PUMPED/CIRCULATED CEMENT TO SURFACE, INSIDE & OUTSIDE 7". PULLED 1" & TOPPED-OFF
WELL.

USED TOTAL OF 145 SACKS CEMENT AND 6 SACKS GEL.

Remarks:

(If additional description is necessary, use BACK of this form.)I DID observe this plugging.

Signed:

RON ROWE

TECHNICIAN

B