

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-01914-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 31-17S-10W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: GEMEINHARDT Well #: 2-B
County: ELLSWORTH Total Vertical Depth: 3252 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

PROD Size: 7 feet: 3242 40 SX CMT
SURF Size: 15 feet: 113

\$105⁶⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/12/2005 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Pumping Method: Pump 50 sxs over parted tubing; perforate @ 1275', 925' & 250'; pump 50 sxs @ 1275' thru tubing; pull tubing to 925'; pump 50 sxs; pull tubing to 250'; and circ to surf.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/12/2005 10:30 AM KCC Agent: VIRGIL CLOTHIER

RECEIVED
KCC DISTRICT #2
JAN 19 2005
WICHITA, KS

Actual Plugging Report:

Perfs:

Ran tubing to 2704' and pumped 50 sacks of cement with cotton hulls. Perforated at 1275' and pumped 50 sacks of cement through tubing. Pulled tubing to 925' and pumped 50 sacks of cement. Pulled tubing to 250' and circulated cement to surface.

60/40 posmix with 4% gel

Swift Services ticket #7631

Parted tubing @ 2704'

Log Tech ticket #13783

RECEIVED
FEB 08 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE

2-8-05

INV. NO.

2005061160