

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-039-20379-00-00

LEASE NAME Davis E

WELL NUMBER 2

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 25TWP. 5S RGE. 30 (W)

COUNTY Decatur

Date Well Completed 3-21-77

Plugging Commenced 1-22-86

Plugging Completed 1-22-86

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4432 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District Office #6

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation L-KC Depth to Top 4055' Bottom 4057' T.D. 4160'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	oil	4055	4057	8-5/8"	278'	0'
				5-1/2"	4155'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged w/325 sx 60/40 Pozmix + 24 sx gel as follows: Spotted 2 sx hulls, 70 sx cmt. at 4160'. Spotted 18 sx gel at 3460'; 100 sx cmt at 1985'; spotted 6 sx gel at 974'; 60 sx cmt at 495'. Pumped down 5-1/2" w/ sx cmt & pressurized to 300 psi. Pumped down 8-5/8" w/90 sx cmt; pressurized to 150 psi. P & A completed. KCC witness Mr. C. Goodrow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Haliburton License No. \_\_\_\_\_

Address Oberlin, Kansas 67749

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Delbert G. Oliver  
3545 NW 58th Street  
 (Address) Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 5 day of February, 19 86

My Commission Expires: 4-24-89  
Deeresa Jo Howarth  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION

Form CP-4  
 Revised 08-84

FEB 6 1986  
 02-06-1986  
 CONSERVATION DIVISION