


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Decatur County. Sec. 25 Twp. 5S Rge. 30W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Benedum-Trees Oil Co.
Lease Name Koerperich #1 Well No. _____
Office Address Benedum-Trees Bldg., Pittsburg 22, Penn.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12/8/55 19____
Application for plugging filed 12/7/55 19____
Application for plugging approved 12/7/55 19____
Plugging commenced 12/8/55 19____
Plugging completed 12/8/55 19____
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4602 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	222 3/4	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled with heavy mud from total depth (4602) up to 220' Set Halliburton plug, using 1/2 sax hulls and 20 sax cement through drill pipe. Filled with heavy mud to 35' Set Halliburton plug using 1/2 sax hulls and 10 sax cement to cellar 0. Job completed 4:00 a.m. 12/9/55

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.
Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF COUNTY OF RUSSELL, ss.
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address) _____

SUBSCRIBED AND SWORN TO before me this 13th day of December, 19 55

Margie Cooper
Notary Public.

My commission expires 1-30-57

PLUGGING
FILE SEC 25 T. 5 R. 30w
BOOK PAGE 24 LINE 4

12-15-1955

15-039-00103-00-00

Benedum-Trees Oil Co.
Koerperich #1

NW NW NW 25-5S-30W
Decatur County, Kansas

Contr: Trans Era Petroleum, Inc.

Elev: 2837 GL

Total Depth: 4602'

Comm: 11/14/55

Comp: 12/9/55

Casing:

10 3/4" @ 222

Cement:

170 sacks of Bulk

FORMATION	DEPTH
Surface Clay	40
Clay-Sand	120
Loose Sand	140
Crystalline sand	170
Sand	185
Shale	630
Shale-Shells	780
Shale - sandy lime	1080
Shale - shells	1390
Shale - shells - pyrite	1650
Sand - shale	1740
Shale - sand-pyrite	1930
Sandy -pyrite	1965
Shale - sand	2070
Shale - lime	2170
Gyp pyrite	2210
Shale - lime	2234
Shale - redbed	2295
Shale - lime	2344
Shale - redbed	2485
Shale - lime	2573
Anhydrite	2613
Shale - lime	3915
Lime	4242
Lime-chert	4264
Lime-shale-chert	4284
Lime - shale	4408
Lime - chert	4427
Chert	4435
Chert - lime	4454
Lime	4491
Lime - shale	4582
Arbuckle	4602

Tops:	Kansas City	3930
	Mississippi	4418

STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

A. P. Honaker

Subscribed and sworn to before me this 13th day of December, 1955.

Margie Cooper
 Notary Public

My commission expires: 1-30-57.

PLUGGING
 FILE SEC 25 T 5 R 30w
 BOOK PAGE 24 LINE 4