

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER <sup>15</sup> 065-23,023-00-00

LEASE NAME DeYoung # 1-33

WELL NUMBER 1-33

330 Ft. from S Section Line

1100 Ft. from E Section Line

SEC. 33 TWP. 9S RGE. 21W (N) or (W)

COUNTY Graham

Date Well Completed 1/6/05

Plugging Commenced 12:30PM 1/6/05

Plugging Completed 3:PM 1/6/05

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR AMERICAN WARRIOR, INC.

ADDRESS P.O. Box 399 Garden City, KS 67846

PHONE# (620) 275-9231 OPERATORS LICENSE NO. 4058

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/5/05 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No Log

Producing Formation None Depth to Top \_\_\_\_\_ Bottom T.D. 3895

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	238	8 5/8	237.85	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:  
 1st Plug @ 1775'W/25sks 10sks In Mouse Hole Circulated 1st Plug 15Minutes W/50Vis Mud  
 2nd Plug @ 1000'W/100sks 15sks In Rat Hole Plugs displaced with mud  
 3rd Plug @ 290'W/40sks Total 200sks 60/40Poz 6%Gel W/1/4#CF/sk By Swift Services, LLC  
 4th Plug @ 40'W/10sks Completed @ 3:00PM 1/6/05

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AMERICAN WARRIOR, INC.

STATE OF Kansas COUNTY OF Finney, ss.

Jody Smith (Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Jody Smith

(Address) P.O. Box 399 Garden City

SUBSCRIBED AND SWORN TO before me this 14<sup>th</sup> day of January, 2005

Mary L. Watts  
 Notary Public

My Commission Expires:



RECEIVED Form CP-4 Revised 05-88

JAN 26 2005

KCC WICHITA Bu