

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Cabot Oil & Gas Corporation
Address: 600 17th Street, Ste. 900N, Denver, CO
Phone: (303) 226-9443 Operator License #: 6120
Type of Well: SWD Docket #: D-15874
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 12-20-04 (Date)
by: Jim Holland (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Glorietta Depth to Top: 1145' Bottom: 1155' T.D. 4450'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 175-20097-00-01
Lease Name: Freeman
Well Number: 2 SWD
Spot Location (QQQQ): _____ - E/2 - SW - NE
3300 Feet from North / South Section Line
1830 Feet from East / West Section Line
Sec. 18 Twp. 33 S. R. 33 East West
County: Seward
Date Well Completed: NA
Plugging Commenced: 12-21-04
Plugging Completed: 12-22-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Glorietta	Water	1145	1155	8-5/8"	1,613'	---

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Test pumped 8-5/8. Mixed 200# hulls & 35 sx cmt to plug perf's from 1145' to 1045', 30 bbl mud spacer to 550', 40 sx 550 to 420 23 bbl mud spacer to 40', 10 sx 40' to 0'. Capped 8-5/8", 3 ft. below G.L.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 27 2005

Name of Plugging Contractor: Sargent & Horton Plugging, Inc. License #: 31151
Address: Rt. 1, Box 49 BA. Tyrone, OK 73951-9731 CONSERVATION DIVISION WICHITA, KS

Name of Party Responsible for Plugging Fees: Cabot Oil & Gas Corporation
State of Colorado County, Denver, ss.

Jay Vashler (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jay Vashler
(Address) 600 17th Street, Ste. 900N, Denver, CO 80202

SUBSCRIBED and SWORN TO before me this 25 day of January, 20 05
Jean A. Arnold Notary Public My Commission Expires: 12-22-06
NOTARY PUBLIC
STATE OF COLORADO
Mail to: KCC - Conservation Division, 130 S. Market Room 2078, Wichita, Kansas 67202
My Commission Expires 12/22/2006