

Fill out COMPLETELY
and return to Conservation Division
at the address below within
30 days from plugging date

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: BP AMERICA PRODUCTION COMPANY

Address: P. O. BOX 3092, WL1-RM 3.201, HOUSTON, TX

Phone: 281-366-2052 Operator License # 5952

Type of Well: GAS Docket # _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/27/04 (Date)

by: DAVID WILLIAMS (KCC District Agent's

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

ST. LOUIS Depth to Top: 5616' Bottom: 5622' T.D. 5765

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number 15- 187-20812-0000

Lease Name RYAN PATRICK, RYAN *KCC BEM 1-26-05 R80ms*

Well Number 1-25

Spot Location (QQQQ) _____ NW _____ SE _____ SE _____

900 Feet from North / South Line of Section

1300 Feet from East / West Line of Section

Sec. 25 Twp. 29S S. R. 40W East West

County: STANTON

Date Well Completed: 03/20/96

Plugging Commenced: 12/29/04

Plugging Completed: 12/29/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled out
	SURFACE CSG	SURFACE	1572'	8 5/8"	1572'	0'
	PRODUCTION CSG	SURFACE	5684'	4 1/2"	5684'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

CHEMICAL CUT CSG AT 5560'; SET CIBP AT 5530' & DUMPED 2 SXS OF CEMENT; SET CIBP AT 2851'; PUMPED 202 SXS OF CEMENT TO FILL 4 1/2" CSG F/950' TO GROUND LEVEL & FILL ANNULUS BETWEEN 4 1/2" & 8 5/8" CSG FROM 950' TO GL; CUT OFF & CAP CSG 5' BELOW GL. WITNESSED BY KCC REP., JIM HOLLAND.

Name of Plugging Contractor: HALLIBURTON SERVICES License # 5287 99997

Address _____

Name of Party Responsible for Plugging Fees: BP America Prod. Co. KCC WICHITA

State of TEXAS County, HARRIS, ss.

SUE SELLERS (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Sue Sellers

(Address) P. O. BOX 3092, WL1-RM 3.201, KATY, TX 77253

SUBSCRIBED and SWORN TO before me this 21ST day of JANUARY, 20 05

Helen K. Zapalac
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas

*KCC
BEM
CP2/3
1-26-05
R80ms*

RECEIVED
JAN 26 2005