

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior Inc.

Address: P.O. box 399 Garden City Kansas 67846

Phone: (620) 275-2963 Operator License #: 4058

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply-Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 1/11/05 (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Arbuckle Depth to Top: 3262' Bottom: 3266' T.D. 3266'

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15 - 053-01915 - 00 - 00

Lease Name: Gemeinhardt

Well Number: B-3

Spot Location (QQQQ): C - S/2 - SW

660' Feet from North / South Section Line

3960' Feet from East / West Section Line

Sec. 31 Twp. 17 S. R. 10 East West

County: Ellsworth

Date Well Completed: 7/19/39

Plugging Commenced: 1/11/05

Plugging Completed: 1/11/05

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes data for Arbuckle formation.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 1275', 925' and 250', 2spf. Ran tbg to 2704'. Pumped 50sx plug w/ 500# hulls. Pulled tbg to 1275', Pumped 50sx plug, Pulled tbg to 925', Pumped 50sx plug, Pulled tbg to 250', Cir cement to surface with 55sx. Hooked up to surface pipe and pumped 30sx. Cir cement up casing. Plugs were 60/40 pos 2% gel.

Name of Plugging Contractor: Swift Services Inc. Express Well Service; Supply License #: 32382-6426 RECEIVED

Address: P.O. Box 466 Ness City Ks. 67560

Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Kansas County, Finney, ss.

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature)

(Address) P.O. Box 399 Garden City Ks. 67846

SUBSCRIBED and SWORN TO before me this 15 day of January

Mary L. Watts Notary Public

My Commission Expires



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC RECEIVED JAN 20 2005 KCC WICHITA

Handwritten initials