

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Gore Oil Company
 Address: P.O. Box 2757, Wichita, KS 67201-2757
 Phone: (316) 263-3535 Operator License #: 5552
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 10-6-04 (Date)
 by: David P. Williams (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 4073' Bottom: 4352' T.D. 4380'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: ¹⁵³ 15-137-20546-00-00
 Lease Name: Rooney
 Well Number: #1
 Spot Location (QQQQ): NE - NE -
600 Feet from North / South Section Line
660 Feet from East / West Section Line
 Sec. 23 Twp. 1 S. R. 35 East West
 County: Rawlins
 Date Well Completed: 5-15-84
 Plugging Commenced: 10-6-04
 Plugging Completed: 10-11-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Oil	0'	336'	8 5/8"	336'	0'
Production	Oil	0'	4377'	4 1/2"	4377'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Move in Murfin and pull rods and tubing. Run tubing back to 3100' for well plugging. Swift on location and pumped 50 sx SMD cement w/400# hulls at 3100'. Pulled tubing to 2100' and pumped 50 sx SMD cement. Pulled tubing to 1000' and circ cement to surface. Pulled rest of tubing and hooked to surface pipe and pumped 23 sx cement w/100# hulls. Topped off casing. Job complete. Used 185 sx total.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382
 Address: P.O. Box 466, Ness City, KS 78560-0466

Name of Party Responsible for Plugging Fees: Gore Oil Company
 State of Kansas County, Sedgwick, ss.

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M. Jack
 (Address) Wichita, KS



SUBSCRIBED and SWORN TO before me this 30th day of November, 20 04
Rebecca K. Crawford My Commission Expires: 3-20-07
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**RECEIVED
DEC 17 2004
KCC WICHITA**

Bur