

State of Kansas



15-163-20511-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 13 1973
CONSERVATION DIVISION
Wichita, Kansas
12-13-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wagoner of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Wagoner guarantees payment of the plugging fee.

Operator's full Name: J. B. Collins, etal

Complete Address: Box 393 Plainville, Ks.

Lease Name: Shaw Well No. 1

Location: NW NW NW Sec. 7 Twp. 6 Rge. (E)(W) 18

County: Rooks Total Depth Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Wagoner was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 620' and displace
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. R. Musser
Conservation Division Agent