



15-163-20231-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Parks of Solar Oil Company has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Solar Oil Company

Complete Address: 1117 Union National Bldg., Wichita, Ks.

Lease Name: Galhoon Well No. 1

Location: NE NE NW Sec. 25 Twp. 6 Rge. 18 (E)(W) XX

County: Rocks Total Depth 3540 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Parks was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with
2 sk cmt.

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1969

Very truly yours,
CONSERVATION DIVISION
Wichita, Kansas

Geo. F. Meany
Conservation Division Agent