



75-163-20494-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1973
CONSERVATION DIVISION
Wichita, Kansas
5-29-73

Dear Sir:

Mr. Niernberger of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt

Complete Address: Box 370 Hays, Ks.

Lease Name: Shaw Well No. 1

Location: SE SE SW Sec. 17 Twp. 6 Rge. (E)(W) 18

County: Rooks Total Depth 3644' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Niernberger was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 700' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent