

State of Kansas



15-163-20530-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 10 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
6-10-74

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Weiler of Shields Drlg. has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Ks.

Lease Name: Sander Well No. 1

Location: S/2 NW SE Sec. 16 Twp. 6 Rge. (E)(W) 18

County: Rooks Total Depth 3280' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Weiler was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 700' and displace  
80 sk cmt thru drill pipe. Heavy mud to 215' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

W. S. Nichols  
Conservation Division Agent JB