



15-163-20150-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. - 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 18 1968
 CONSERVATION DIVISION
 Wichita, Kansas

11-18-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Cooke of Abercrombie Drlg. has this date requested permission to plug the following described well:

Mr. Cooke guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company

Complete Address: 1130 Wichita Plaza Wichita, Ks.

Lease Name: Vehige Well No. 1

Location: NE SW NW Sec. 6 Twp. 6 Rge. 20 (E)(W) XX

County: Rooks Total Depth 3573 Oil Well

Gas Well Input Well SWD Well D & AX Lost Hole

Mr. Cooke was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1400' and displace
60 cu. ft. cement thru drill pipe. Heavy mud to 215' set cementing plug
and displace 15 cu. ft. cement thru drill pipe. Heavy mud to 40' set
cementing plug, 1/4 sc hulls and 8 cu. ft. cement to base of cellar.
Plug rat hole with 2 sc cement.

Very truly yours,

Leo F. Massey
 Conservation Division Agent