



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 5 1970

CONSERVATION DIVISION

Wichita, Kansas

105-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Buffington of Red Tiger has this

date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Glen N. Rupe

Complete Address: 222 Brown Bldg., Wichita, Ks.

Lease Name: Witt Well No. 1

Location: NW NE SE Sec. 4 Twp. 6 Rge. (E)(W) 20

County: Rooks Total Depth 3607 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Buffington was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace

70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent