



15-163-20175-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 25 1971
CONSERVATION DIVISION
Wichita, Kansas
6-25-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wilber Crandall of Knight Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Crandall guarantees payment of the plugging fee.

Operator's full Name: Rosen Oil Corporation,

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: Steele Well No. 1

Location: 50' FC of S/2-SW/4 Sec. 4 Twp. 6 Rge. (E)(W) 20

County: Rooks Total Depth 3623 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Crandall was instructed to plug the well as follows:

226'-- 7 5/8" Surface casing, cement circulated with 135 Sx. (6 3/4" Hole).
3621'-- 4 1/2" Production casing cemented on bottom with 125 Sx. Top perfor-
ations @ 3615'.

Sand well back to 3600' and set 4 Sx. cement with dump bailer. Pull 4 1/2"
casing and squeeze well with 3 sacks hulls, 25 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,

W. L. Nichols

Conservation Division Agent