

State of Kansas



15-163-20024-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 2 1967
6-2-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lahr of B-B Drilling Co. has this
date requested permission to plug the following described well:

Mr. Lahr guarantees payment of the plugging fee.

Operator's full Name: Alladdin Petroleum Company etal

Complete Address: 809 Petroleum Bldg. Wichita, Kansas

Lease Name: Buss Well No. 1

Location: NE SE SE Sec. 4 Twp. 6 Rge. 20 (E)(W) X

County Rooks Total Depth 3629 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahr was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace
20 sc cement thru drill pipe. Heavy mud to 210' and displace 20 sc cement
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and
8 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Geo F. Massey
Conservation Division Agent