

DISTRICT CONSERVATION AGENT'S REPORT

15-163-03158-00-00

R

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW-NE-NW

SEC. 12 TWP. 6 RGE. 18W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

W

I have today completed supervision of plugging of:

Well No. 2 Lease Faubion

Operator Calkey Oil Co Address #929 Kennedy Bldg - Tulsa Okla

Field \_\_\_\_\_ County Nowata

Total Depth 3262 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 1402 ft - Circulated with cement  
7" casing set at 3156 ft + cemented with 200 sacks of  
cement - Filled hole back from bottom to 3100 ft - Put  
in 5 sacks of cement at 3100 ft - Ripped off + recovered  
2490 ft of 7" casing. Filled with mud to 1000 ft - Plug +  
10 sacks cement at 1000 ft - Mud to 200 ft - Plug + 10 sacks  
cement at 200 ft - Mud to within 20 ft of the surface  
Plug + 5 sacks cement - filling hole up to the surface  
Mr. Bailey - Pipe Puller  
C. M. Stough  
District Conservation Agent

Date 11-26-47

**PLUGGING**  
FILE SEC 12 TWP 6 R 18W  
BOOK PAGE 2 LINE 4

11-29-47