

14 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-30134-00-00

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 28 1966  
2-28-66  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Natl Associated Petro.

Complete Address: 502 Ritz Bldg Tulsa Okla

Lease Name Fashion Well No. 1

Location Nw. Sec. Sw Sec. 1 Twp. 6 Rge. 18 (E) (W)

County Rooks Total Depth 3440

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Thoroughbred Oil Co.

Address: Tulsa Okla. License No.     

Operation Completed: Hour 4:15 P Day 25 Month Feb Year 1966

The Above well was plugged as follows:

Total Depth 3440 8 1/8 set at 254  
Gunned pits circulated hole with heavy mud, set cementing plug at 540 ft.,  
and displaced 20 sac cement thru drill pipe, heavy mud to 240 ft., set cementing  
plug and displaced 20 sac cement, heavy mud to 40 ft., set cementing plug  
1/2 sac hulls and 10 sac cement, cementing to base of collar.

I hereby certify that the above well was plugged as herein stated. Gilbert P. Leiker  
Signed: Gilbert P. Leiker  
Well Plugging Supervisor

INVOICED

DATE 3/1/66  
INV. NO. 2995-W