

DISTRICT CONSERVATION AGENT'S REPORT

15-163-02474-00-00

R

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 05-54

LOCATION NW NW NE

SEC. 12 TWP. 6 RGE. 18 W

Dry Hole  Abandoned Oil Well  Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease Faubion

Operator Honaker Drg Co Address Great Bend, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3155 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 226' circulated with cement - 5 1/2" at 3154' with  
175 sax cement behind, perf at 3110' and squeezed with 650 sax  
cement, perf at 2810' and squeezed with 275 sax cement.

Lane wells plugs t 2880', perf at 2812 to 24'.

Filled with chat to 2800', set 4 sax cement with dump bailer,  
pulled 2040' 5 1/2", gunned mud pits and pumped hole full rotary mud,  
pumped cementing plug to 270', followed by 90 sax cement filling  
hole to bottom cellar with cement.

Mudding and Cementing by Sun Cementing Co .

RECEIVED  
STATE CORPORATION COMMISSION

MAR 20 1951

CONSERVATION DIVISION  
Wichita, Kansas

*Edna Perry*  
District Conservation Agent

Date W 3-15-51

**PLUGGING**  
FILE SEC 1 T 6 R 18 W  
PAGE 65 LINE 34