

KANSAS

*J*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20131-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leo J. Dreiling Oil Company

Complete Address: Victoria, Kansas

Lease Name Shaw Well No. 1

Location NW SE Sec. 8 Twp. 6 Rge. 18 (E) (W) X

County Rooks Total Depth 3510

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Go, Tools

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 4P Day 29 Month 9 Year 1968

The Above well was plugged as follows:

RTD 3510' 8 5/8 csg set at 171' cwc. Cmt. Mat. 50-50 poz cmt. W/6% total Gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 1 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: Leo J. Massey  
Well Plugging Supervisor

INVOICED

DATE 10/1/68

INV. NO. 8551-11

10-1-68