

P

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 13 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
12-13-73

15-163-20511-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name J. B. Collins, etal

Complete Address Box 393, Plainville, Kansas

Lease Name Shaw Well No. 1

Location NW NW NW Sec. 7 Twp. 6 Rge. (E) (W) 18

County Rooks Total Depth 3505'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 12:30 P Day 12 Month 12 Year 1973

The above well was plugged as follows:

RTD 3505' 8 5/8 esg set at 215' cwc Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 620' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

      

      

      

      

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey  
Well Plugging Supervisor

INVOICED

DATE 12/14/73  
INV. NO. 8297-W