

KANSAS

Form CP-3
Rev. 6-4-68

28
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20494-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1973

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don E. Pratt

Complete Address Box 370 Hays, Kansas *5-29-73*

Lease Name Shaw Well No. 1

Location SE SE SW Sec. 17 Twp. 6 Rge. (E) (W) 18

County Rooks Total Depth 3644'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Co.

Address Wichita, Kansas License No.

Operation Completed: Hour 12:15 P Day 21 Month 5 Year 1973

The above well was plugged as follows:

RTD 3644' 8 5/8 csg set at 266' cwc Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 700' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leo J. Massey*
Well Plugging Supervisor

DATE 5/31/73
INV. NO. 7430-W