

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

13-163-20479-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1974
9-9-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. Scott Ritchie
Complete Address 412 Union Center Wichita Kansas
Lease Name M^c Queen Well No. 1
Location SW-NE-SW Sec. 16 Twp. 6 Rge. 18 (E) (W)
County Rooks Total Depth 3575
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling
Address Box 176 Chase Ks. License No. 683

Operation Completed: Hour 11:30 AM Day 5 Month 9 Year 1974

The above well was plugged as follows:

Elev. 1983 - map Dakota Top. 1400
8 5/8" - 208' 5 1/2" - 3510 Recovered 2591'
Perf - 3266 Plug @ 3200' Dumped 20' sand
and 4 sacks cement.
Pumped down 8 5/8" 3 sacks Hulls
20 sacks Gel-70 sacks cement 50/50 pozmix 6% Gel-
10 sacks Gel-1 sack Hulls - Released Plug
50 sacks cement 50/50 pozmix 6% Gel- Allied pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: Dale F. Batchelor
Well Plugging Supervisor

INVOICED

DATE 9/10/74
INV. NO. 9856-W