

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT  
15-163-20094-00-00  
RECEIVED  
STATE CORPORATION COMMISSION  
JAN 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
1-6-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leo J. Dreiling Oil Company  
Complete Address R. R. # 2 Victoria, Kansas 67671  
Lease Name McQueen Well No. 1  
Location NW NW NW Sec. 16 Twp. 6 Rge. (E) (W) 18  
County Rooks Total Depth 3572  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Russ Casing Pulling Inc.  
Address Box 1082 Great Bend, Kansas License No. 623  
Operation Completed: Hour 3P Day 2 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 3575 8 5/8 csg set at 175' cwc  
5 1/2 csg set at 3572 cw 150 sk cmt.  
5 1/2 csg perf. (320 1/2')  
Set 5 1/2 plug at 3150' poured 10' sd and dumped 4 sk cmt W/dump bailer.  
Cutoff and recovered 2050' of 5 1/2 csg.  
pumped down 8 5/8 csg with 20 sk gel W/5 sk hulls, 70 sk cmt 6% gel, 8 sk gel and  
50 sk cmt 6% gel.  
Gmt. (0-200) gel (200-500) Gmt. (500-800) gel (800-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ben J. Murrin  
Well Plugging Supervisor

DATE 1-6-70  
INV. NO. 1214-W