

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20175-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 25 1971
CONSERVATION DIVISION
Wichita, Kansas
6-25-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rosen Oil Corporation,

Complete Address 200 Sutton Place, Wichita, Kansas.

Lease Name Steele Well No. 1

Location 50' FC of S/2-SW/4 of Sec. 4 Twp. 6 Rge. (E) (W) 20

County Rooks Total Depth 3623'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 11:00 AM Day 23 Month 6 Year 1971

The above well was plugged as follows:

226'--~~8~~ 5/8" Surface casing, cement circulated with 135 Sx. (6 3/4" Hole).
3621'--~~4~~ 1/2" Production casing cemented on bottom with 125 Sx. Top perforations @ 3615'.

Sanded well back to 3600' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing
(1012') and squeezed well initially with 3 sacks hulls and 15 sacks gel and followed
with 85 cu. ft. cement from 1150' to 800' then 10 sacks gel from 800' to 250' and
finally 65 cu. ft. cement from 250' to bottom of cellar. Maximum pump-in pressure-
150#. Final shut-in pressure-50#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 6/25/71
INV. NO. 3914-W