

KANSAS

*Y*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 3 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas

4-3-72

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Bradem -Deem, Inc. 15-163-20304-00-00  
Complete Address Suite 520 200 E. 1st. Wichita, Kansas 67202  
Lease Name Hansen Estate "A" Well No. 1  
Location NW SW SE Sec. 2 Twp. 6 Rge. (E) (W) 20  
County Rooks Total Depth 3615'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Rockhold Engineering  
Address Box 698 Great Bend, Kansas 67530 License No. 670  
Operation Completed: Hour 12 N Day 31 Month 3 Year 1972

The above well was plugged as follows:

Total Depth 3615' 8 5/8 csg set at 229' cwc  
5 1/2 csg set at 3613' cw 150 sk cmt.  
5 1/2 csg PBTD 3566' with top perf. (3544)  
Filled 5 1/2 csg W/sd (3500-3566) dumped 5 sk cmt W/dump bailer. (3465-3500)  
Cutoff and recovered 2600' of 5 1/2 csg.  
Pumped down 8 5/8 csg with 18 sk gel & water W/500 lbs hulls. -70 sk cmt. -10 sk gel & water -released 8 5/8 plug and pumped 50 sk cmt. by Allied cementing co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo A. Smalley  
Well Plugging Supervisor

DATE 4-3-72

INV. NO. 5455-W