

RECEIVED

MAY 22 2003

KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

15-163-22426-0000

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-163-22426-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Bach Oil Production, Inc. KCC LICENSE # 31569  
(owner/company name) (operator's)

ADDRESS P.O. Box 723 CITY Alma

STATE Nebraska ZIP CODE 68920 CONTACT PHONE # (308) 928-2221

LEASE Wallgren A WELL# 4 SEC. 6 T. 06S R. 20 (xxxx/West)

- SE-SE - SW SPOT LOCATION/QQQQ COUNTY Rooks

330 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)

2970 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#

CONDUCTOR CASING SIZE  SET AT  CEMENTED WITH  SACKS

SURFACE CASING SIZE 8-5/8 SET AT 360' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 4-1/2 SET AT 3516' CEMENTED WITH 125 SACKS

DV set @ 1622' Cemented with 365 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3252-3255' & 3270-3275'

ELEVATION 2126 KB T.D. 3519' PBDT 3495' ANHYDRITE DEPTH 1618'

(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING SPOT 25 SX+2 HULLS @ 3225' PULL TO 1635'. PUMP 75 SX TO SURFACE. PULL TUBING AND SQUEEZE AT SURFACE AS NEEDED. PUMP 25 SX DOWN 8-5/8-4-1/2 ANNULUS W/25 SX + 2 HULLS. ALL CEMENT 60/40 POZ+10% GEL.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? YES

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jason Bach PHONE# (785) 476-5254

ADDRESS P.O. Box 723 City/State Alma, Nebraska 68920

PLUGGING CONTRACTOR Allied Cementing Co., Inc. KCC LICENSE #

(company name) (contractor's)

ADDRESS P.O. Box 31 Russell, KS 67665-0031 PHONE # (785) 483-2657

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) September 2003

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR  xxxx

DATE: 5/20/03 AUTHORIZED xxxxxxx/AGENT: Dan Freed

(signature)

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    John Wine, Commissioner    Robert E. Krehbiel, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Bach, Jason dba Bach Oil Production  
RR 1, Box 28  
Phillipsburg, KS 67661

May 22, 2003

Re: WALLGREN #4  
API 15-163-22426-00-00  
SESESW 6-6S-20W, 330 FSL 2970 FEL  
ROOKS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550

Sincerely



David P. Williams  
Production Supervisor