

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM

(File One Copy)

API NUMBER 15-163-20,326-00-01
1-27-77 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Hellar Drilling Company, Inc. OPERATOR'S LICENSE NO. 5015
ADDRESS 125 N. Market - Suite 1422
Wichita, KS 67202 PHONE # (316) 267-2845

LEASE (FARM) WITT WELL NO. 1 WELL LOCATION NW NE SE COUNTY Rooks
SEC. 4 TWP. 6 RGE. 20 (~~BYOK~~ W) TOTAL DEPTH 3610 PLUG BACK TD 3550

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 207 CEMENTED WITH 150 SACKS

CASING SIZE 4 1/2 SET AT 3579 CEMENTED WITH 125 SACKS

PERFORATED AT 3462-72, 3487-93, 3503-05

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Run thb to TD cement up 325 sks 65/35 Poz 5% gel 1/4#

Flo seal 1 sk. 1000# hulls

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? None
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Near Future

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl Gilpin PHONE # (913) 625-6702
ADDRESS Box 146
Hays, KS 67601

PLUGGING CONTRACTOR Allied Cementing Co. Inc. LICENSE NO. None
ADDRESS P O Box 31 PHONE # (913) 483-2627
Russell, KS 67665

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.
HELLAR DRILLING COMPANY, INC.

SIGNED: [Signature]
(Operator or Agent) President-D. L. Hellar

DATE: September 20, 1990

(4)

RECEIVED
STATE CORPORATION COMMISSION
9-24-90
SEP 24 1990
CONSERVATION DIVISION
Wichita, Kansas

508 East Murdock
Wichita, Kansas

OCT 24 1970

K. U. S. LIBRARY

4-6-20W
NW NE SE

15-163-20326-00-01

DRILLERS LOG

No. 1 Witt

CASING RECORD:

8 5/8" @ 209'
w/150 sx cement

TOTAL DEPTH: 3607'

COMPANY:

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: September 22, 1970

COMPLETED: October 2, 1970

DESCRIPTION:

NW NE SE
4-6S-20W
Rooks County,
Kansas

ELEVATION: 2109' RB

Dry/Reagan

FORMATION

FROM

TO

REMARKS

Sod, Clay
Shale
Sand
Shale
Shale & Shells
Anhydrite
Shale & Lime
Lime
Cong. Shale
Lime
Lime & Sand

0
140
1255
1435
1490
1706
1736
3185
3543
3561
3587

140
1255
1435
1490
1706
1736
3185
3543
3561
3587
3607

S Log Lips
** Anhydrite 1706*
** Lapeka 3104*
Hebner 3300
Br Ln 3325
LKC 3342
Reagan sd 3589

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice



Subscribed and sworn to before me this 5 day of October, 1970.

Virginia K. Albert
Notary Public
"OWWO"

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1970

My Commission Expires:

July 23, 1974

Co: Castle Oil Co.

Well: #1 Witt

Card Issued: 1-27-77

IP: P 13 BOPD + 1 BWPD LKC 3467-3505

New Info: MIRT - wash down to 3610, set 4 1/2
3579/125 sx, mict-pf 3467-72, 3487-
93 & 3503-05, ac 3000 & rec ld, re-ac
1500, rec ld & pop



Kansas Corporation Commission

| | |
|--------------------|--------------------|
| MIKE HAYDEN | GOVERNOR |
| KEITH R. HENLEY | CHAIRMAN |
| RICH KOWALEWSKI | COMMISSIONER |
| JACK SHRIVER | COMMISSIONER |
| JUDITH MCCONNELL | EXECUTIVE DIRECTOR |
| FRANK A. CARO, JR. | GENERAL COUNSEL |

CONSERVATION DIVISION
 SHARI FEIST ALBRECHT, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

September 25, 1990

Hellar Drilling Company, Inc.
125 N. Market, Suite 1422
Wichita, KS 67202

Witt #1
NW NE SE 04-06-20W
Rooks County, KS
API No. 15-163-20,326-00-01

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

District: #4, 2301 E. 13th
Hays, KS 67601
(913) 628 - 1200