

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1978

11-28-78

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 039-20432-00-00 (of this well)
Lease Owner Nelson Petroleum Company
Address 2301 Fourth National Bank Bldg., Tulsa, Oklahoma 74119
Lease (Farm Name) Phyllis McKay Well No. 1
Well Location NE NW NW Sec. 13 Twp. 5S Rge. 29W (E) (W) X
County Decatur Total Depth 4390' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 6:00 p.m., 11-17-78.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 So. 2nd Street, Hill City, KS

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Nelson Petroleum Company

Address 2301 Fourth National Bank Bldg., Tulsa, Oklahoma 74119

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge
Date: November 27, 1978

OPERATOR: Nelson Petroleum Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Phyllis McKay #1
 LOCATION: NE NW NW, Section 13-5S-29W
 Decatur County, Kansas
 SPUD DATE: November 8, 1978
 COMPLETION DATE: November 17, 1978

0	271	Surface Soil, Sand & Shale
271	1226	Shale
1226	2065	Shale & Sand
2065	2380	Sand & Shale
2380	2476	Shale
2476	2511	Anhydrite
2511	2625	Shale
2625	2842	Shale & Lime
2842	3083	Shale
3083	3445	Lime & Shale
3445	3908	Shale & Lime
3908	3910	Lime
3910	3952	Shale & Lime
3952	3960	Lime
3960	4022	Lime & Shale
4022	4027	Shale & Lime
4027	4095	Lime
4095	4129	Lime & Shale
4129	4205	Shale & Lime
4205	4305	Lime
4305	4390	Lime & Shale
	4390	Rotary Total Depth

Spud hole at 5:00 p.m., November 8, 1978. Drilled 271' of 12 1/4" hole. Ran 6 joints of 8 5/8" - 28# casing. Set at 271' with 200 sacks of 60/40 posmix 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 11:00 p.m., November 8, 1978.

T.D. 4390'. Set 1st plug at 1400' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' with 10 sacks, a solid bridge. Cemented with 50/50 posmix, 6% gel. Job was complete at 6:00 p.m., November 17, 1978.

SAMPLE TOPS:

Anhydrite 2476'
 B/Anhydrite 2511'

RECEIVED
 STATE CORPORATION COMMISSION

NOV 28 1978

1128-78

CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Phyllis McKay #1, NE NW NW, Section 13-5S-29W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid as of this 27th day of November, 1978.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

State of Kansas



15-039-20432-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

November 22, 1978

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Phyllis McKay
Description	NE NW NW Sec. 13-5-29W
County	Decatur
Total Depth	4398'
Plugging Contractor	Abercrombie Drilling, Inc.


**Nelson Petroleum Co.
2301 Fourth National Bank Building
Tulsa, Oklahoma 74149**

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Baithazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above
named well.