

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 023 - 20,163 - 0000 (of this well)

Lease Owner Thunderbird Drilling, Inc.

Address P.O. Box 18407- Wichita, Kansas 67218

Lease (Farm Name) Eggers "C" Well No. 1

Well Location SE NW Sec. 25 Twp. 5S Rge. 37W (E) (W)

County Cheyenne Total Depth 4660 Field Name _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X

Well Log attached with this application as required Yes

Date and hour plugging is desired to begin 8:00 A.M. 1/18/81

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

E.R. Cook Address P.O. Box 864, Great Bend, Ks. 67530

Plugging Contractor Thunderbird Drilling, Inc. License No. _____

Address Same as above

Invoice covering assessment for plugging this well should be sent to:

Name Thunderbird Drilling, Inc.

Address Same

and payment will be guaranteed by applicant or acting agent.

RECEIVED
STATE CORPORATION COMMISSION
2-18-81
FEB 18 1981

Signed: [Signature]
Applicant or Acting Agent

Date: February 5, 1981

CONSERVATION DIVISION
Wichita, Kansas

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG


IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 25 T. 5S R. 37W^E_W

Loc. SE NW

County Cheyenne

640 Acres
N



Locate well correctly

Elev.: Gr. 3244

DF _____ KB 3249

API No. 15 — 023 — 20,163 - 00-00
County Number

Operator
Thunderbird Drilling, Inc.

Address
P.O. Box 18407- Wichita, Kansas 67218

Well No. 1 Lease Name Eggers "C"

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Thunderbird Drilling, Inc. Geologist Paul Montoia

Spud Date 1/7/81 Date Completed 1/18/81 Total Depth 4660 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 3/4	8 5/8"	24#	442'	com	325	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED
FEB 18 1981
2-18-81
CONSERVATION DIVISION
Wichita, Kansas

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Thunderbird Drilling, Inc.** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. **1** Lease Name **Eggers "C"** Dry Hole

S 25 T 5S R 37 ^{WE}/_W

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 /30-60-30-60, rec. 200' mw, 654' sw w/scum of oil, FP 98-415#, BHP 1276-2137#	4086	4148		
DST #2 /30-60-30-60, rec. 1677' mw, FP 158- 1081#, BHP 1334-1315#	4242	4270		
DST #3 /30-60-30-60, rec. 15' hocom, FP 27-39# BHP 1178-886#	4298	4324		
DST #4 /30-60-30-60, rec. 15' mud w/sho oil, FP 9-9#, BHP 11-11#	4511	4525		
<u>From</u> <u>To</u> <u>Description</u>				
0	442	Surface Hole		
442	1750	Shale		
1750	2150	Shale & Sand		
2150	3144	Shale & Shells		
3135	3154	Anhydrite		
3154	3392	Shale & Lime		
3392	3570	Shale		
3570	4660	Lime		
4660		R.T.D.		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____


 Signature **Burke Krueger**
 Vice-President
 Title
 2-6-81
 Date

State of Kansas



15-023-20163-00-00

JOHN CARLIN
G. C. LOUX
WANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Bldg.
WICHITA, KANSAS 67202

February 20, 1981

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Eggers "C"
Description	SE NW
Section	25-5S-37W
County	Cheyenne
Total Depth	4660'
Plugging Contractor	Thunderbird Drlg. , Inc.

Thunderbird Drlg., Inc.
Box 18407
Wichita, Ks. 67218

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,


For Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Palco, Kansas, 67657

is hereby assigned to supervise the plugging of the above named well.