

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # ²⁰⁷⁹⁴ ~~15-119-20-794-00-00~~ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date

WELL OPERATOR BRG Petroleum (owner/company name) KCC LICENSE # 30157 ^{32416 4/05} (operator's)

ADDRESS 7134 S. Yale CITY Tulsa

STATE Oklahoma ZIP CODE 74136 CONTACT PHONE # (918) 496-2626

LEASE Hallock WELL# 1-31 SEC. 31 T. 32S R. 28W (East/West)

NW - SW - SPOT LOCATION/OOOO COUNTY Meade

2310 FEET (in exact footage) FROM (S) N (circle one) LINE OF SECTION (NOT Lease Line)

4290 FEET (in exact footage) FROM (E) W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL. ___ GAS WELL. X D&A ___ SWD/ENHR WELL. ___ DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 1470 CEMENTED WITH 550 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 5725 CEMENTED WITH 250 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5572-5582

ELEVATION 2527 T.D. 5725 PBDT _____ ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING displace hole with 9.5# mud, set CIBP 50 foot above perfs,

20 foot cement on top, cut and pull casing, run tubing to 1570 feet, pump 75 sacks

tag and 20 sacks 60-to surface, weld on steel ID plate

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? _____

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

H&K Plugging & Salvage PHONE# (806) 665-2550

ADDRESS P.O. Box 2742 City/State Pampa, Texas 79066-2742

PLUGGING CONTRACTOR H&K Plugging & Salvage KCC LICENSE # 31705

ADDRESS P.O. Box 2742 Pampa, Texas 79066 (company name) (contractor's)
PHONE # (806) 665-2550

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____


PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1-3-05 AUTHORIZED OPERATOR/AGENT: Denny Lee (signature)

RECEIVED

FEB 07 2005

KCC WICHITA



CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

BRG Petroleum Corporation
7134 S. Yale STE 600
Tulsa, OK 74136

February 08, 2005

Re: HALLOCK #1-31
API 15-119-20794-00-00
NWSW 31-32S-28W, 2310 FSL 4290 FEL
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely

David P. Williams
Production Supervisor