

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-051-22,182-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR The Dane G. Hansen Trust KCC LICENSE # 5285
(owner/company name) (operator's)

ADDRESS P. O. Box 187 CITY Logan

STATE Kansas ZIP CODE 67646 CONTACT PHONE # (785)-689-4816

LEASE Storm WELL# 5 SEC. 34 T. 13 R. 20 (East/West)

SE - SW - NE - SPOT LOCATION/0000 COUNTY Ellis

2970 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

1650 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL D&A SWD/ENHR WELL DOCKET#

D.V. Tool @ 1505' w/375 sx Cmt. Circulated
CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 203' CEMENTED WITH 175 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3830' CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3676-80; 3657-60; 3646-49; 3568-72;

ELEVATION 2248 T.D. 3840 PSTD 3548-54; 3519-22 P-1 @ 3800'
(G.L./K.B.) ANHYDRITE DEPTH 1554'
(Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK X JUNK IN HOLE

PROPOSED METHOD OF PLUGGING According to the Rules and Regulations of the **RECEIVED**

State of Kansas

FEB 07 2005

(If additional space is needed attach separate page)

KCC WICHITA

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Richard L. Wallgren, Sr. PHONE# (785)-689-4816

ADDRESS P. O. Box 187 City/State Logan, Kansas 67646

PLUGGING CONTRACTOR Allied Cementing Company, Inc. KCC LICENSE # 99996

(company name) (contractor's)
ADDRESS P. O. Box 31, Russell, KS 67665 PHONE # 785-483-2627

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) As soon as possible.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: Feb. 2, 2005 AUTHORIZED OPERATOR/AGENT:

(Signature)
Richard L. Wallgren, Sr.

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG


API No. 15 — 051 — 22,182
County Number

S. 34 T. 13SR. 20 R
W

Loc. SE SW NE

County Ellis

640 Acres
N



Locate well correctly

Elev.: Gr. 2248

DF 2250 KB 2253'

Operator
Dane G Hansen Trust

Address
P O Box 187, Logan, KS 67646

Well No. 5 Lease Name Storm

Footage Location
330 feet from (N) (S) line 330 feet from (E) (W) line

Principal Contractor Geologist
C-G Drilling Co., Inc. Jerry Jespersen

Spud Date Date Completed Total Depth P.B.T.D.
12/30/80 1/9/81 3840

Directional Deviation Oil and/or Gas Purchaser
Phillips Petroleum

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

| Purpose of string | Size hole drilled | Size casing set (in O.D.) | Weight lbs/ft. | Setting depth | Type cement | Sacks | Type and percent additives |
|-------------------|-------------------|---------------------------|----------------|---------------|-------------|-------|----------------------------|
| SURFACE | 12 1/4" | 8 5/8" | 24# | 207' | Common | 175 | 3% CC 2% Gel |
| PRODUCTION | | 5 1/2" | 14# | 3830' | Salt Sat | 175 | |
| | | | | | 2 Staged | | |
| | | | | | 50-50Poz | 375 | |
| | | | | | 6% Gel | | |

LINER RECORD

PERFORATION RECORD

| Top, ft. | Bottom, ft. | Sacks cement | Shots per ft. | Size & type | Depth interval |
|----------|-------------|--------------|---------------|-------------|----------------|
| | | | | | |

| Size | Setting depth | Packer set at |
|-------|---------------|---------------|
| 2 1/2 | 3784 | |

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

| Amount and kind of material used | Depth interval treated |
|----------------------------------|------------------------|
| | |

RECEIVED
FEB 07 2005
KCC WICHITA

INITIAL PRODUCTION

| | |
|--|---|
| Date of first production 3/18/81 | Producing method (flowing, pumping, gas lift, etc.) pumping |
| RATE OF PRODUCTION PER 24 HOURS | Oil 10 bbls. Gas X X MCF Water 90% bbls. Gas-oil ratio X X CFPB |
| Disposition of gas (vented, used on lease or sold) vented | Producing interval(s) 3854-68 |

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

| | | |
|---------------------------------|---------------------|--|
| Operator Dane G Hansen Trust | | DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil |
| Well No. 5 | Lease Name Storm | |
| S 34 T13S R 20 ^W | | |

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

| FORMATION DESCRIPTION, CONTENTS, ETC. | TOP | BOTTOM | NAME | DEPTH |
|--|------|--------|------------|-------|
| ANHYDRITE | 1554 | +699 | Heebner | 3472 |
| BASE/KANSAS CITY | 3789 | -1536 | Toronto | 3498 |
| MARMATON | 3793 | -1540 | Lansing/KC | 3517 |
| CONGLOMERATE | 3818 | -1565 | | |
| ARBUCKLE | 3828 | -1575 | | |
| RTD | 3840 | -1587 | | |
| DST #1: 3508-3528' PLUGGED TOOL DST #2: 3508-3528' 15-45-60-45 REC 960' GIP, 120' GO, 120' GOCM, IBHP 1072#, FBHP 905#, IFP 52#, FFP 95# DST #3: 3588-3595' REC 180' MUD, IBHP 822#, FBHP 402#, IFP 116#, FFP 116# DST #4: 3612-3627' 15-45-60-45 REC 60' MUD, IFP 31#, FFP 52#, IBHP 926# FBHP 864# DST #5: 3638-3730' 15-45-15-45 REC 945' MUD, IBHP 1468#, FBHP 1354#, IFP 391# FFP 529# | | | | |

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

| | |
|---------------|----------------------------|
| Date Received | <i>Debra Heersche</i> |
| | Signature |
| | Debra Heersche, Office Mgr |
| | Title |
| | 1/21/81 |
| | Date |

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Hansen, Dane G. - Trust
PO Box 187
Logan, KS 67646-187

February 10, 2005

Re: STORM #5
API 15-051-22182-00-00
SESWNE 34-13S-20W, 2970 FSL 1650 FEL
ELLIS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550