

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

15-163-01108-00-00

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner Colorado Oil and Gas Corporation Address Box 1030, Wichita, Kansas
(Applicant)

Lease (Farm Name) STEELE Well No. 1

Well Location N/2 NW NW Sec. 9 Twp. 6 Rge. (E) (W) 20

County Rooks Field Name (if any) S.E. Ray

Total Depth 3639 Oil Gas Dry Hole

Was well log filed with application? Yes If not, explain: _____

Date and hour plugging is desired to begin September 27, 1957

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well for owner _____

O. B. Grubbs Address Plainville, Kansas

Plugging Contractor West Supply Co., Inc.

Plugging Contractor's License No. 14

Address Box 506 Chase, Kansas

Invoice covering assessment for plugging this well should be sent to _____

Colorado Oil and Gas Corporation Address Box 1030, Wichita, Kansas

and payment will be guaranteed by applicant.

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1957
CONSERVATION DIVISION
Wichita, Kansas
9-28-57

Bill K. Henrichs
Applicant or Acting Agent
Bill K. Henrichs
Date 9-27-57

PLUGGING
FILE SEC 9 T 6 R 20W
BOOK PAGE 43 LINE 43



15-163-61108-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS
September 27, 1957


Well No. L.
Lease Steele
Description QN/S NE1 SW 9-6-30W
County Neosho
File No. 48-10

Colorado Oil & Gas Corporation
Box 1030
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas

Very truly yours,


Jewel M. Ogden
Director of Conservation Division

cc:
District Plugging Supervisor

15-163-01108-00-00

THE DERBY OIL COMPANY &
CROW DRILLING COMPANY

Record of Well No. 1
 Location C N $\frac{1}{2}$ NW NW
 Contractor Crow Drilling
 Drilling Commenced 12-1-41
 Drilling Completed 1-1-42

Steele Farm
 Sec. 9 Twp. 6 Rge. 20W
 County: Rocks
 Elevation

Casing Record

Size	Feet	Kind	Weight	
8 5/8	161	New Surface		Cemented with 85 sacks Ideal cement by Halliburton
4 $\frac{1}{2}$ O.D.	3602	E. W.		Cemented with 85 sacks Dewey cement by Halliburton

Formation	Bottom		
Sand	0-63	Lime	2606
Shale & Shells	105	Shale	2609
Shale	138	Lime & Shale	2644
Shale & Shells	155	Shale	2661
Shale	1034	Lime	2707
Shale & Shells	1103	Shale	2721
Shale	1172	Shale & Lime	2825
Lime	1196	Shale	2847
Shale & Lime	1250	Lime	2863
Shale	1269	Shale	2882
Sand	1447	Shale & Lime	2922
Red Rock & Shale & Shells	1620	Shale	2982
Shale	1719	Shale & Lime	2992
Sand	1759	Lime	3014
Broken Lime	1831	Shale & Lime	3034
Shale	1856	Lime	3045
Red Ded	1877	Shale	3065
Shale & Shells	2022	Lime	3077
Shale	2160	Shale	3086
Broken Lime	2185	Lime & Shale	
Shale & Lime Streaks	2225	streaks	3147
Shale	2359	Lime	3200
Lime	2372	Cherty Lime	3218
Shale	2409	Lime	3405
Lime	2422	Lime & Streaks	
Shale & Lime Streaks	2480		
Shale	2590		

OPEN PLUGGING		3430
FILE	SEC 9 T 6 R 20W	3498
BOOK	PAGE 48	LINE 43

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1957
REGISTRATION DIVISION
1955

Lime & Chert	3521
Lime	3569
Shale	3600
Lime	3625
Sand	3628
Granite	3639 T.D.

D. P. 3639 T.D. Hole caved C.
O. and Sub. 28.14 oil in 4 hrs.
25' of cavings back in hole -
clean out and sub. $6\frac{1}{2}$ oil per
hour for 2 hours. Hole caved
again - cleaned out. Run rods
and tubing.
Pump Potential 183 Oil - No
water.

15-463-01108-00-00

Geological Data

Lansing	3359
Precambrian Sand Arkose	3613
T. D.	3639

RECEIVED
STATE COMMISSION

SEP 2 1937
CONSERVATION DEPARTMENT
Wichita, Kansas

PLUGGING

FILE SEC. _____ T. _____ R. _____
BOOK PAGE _____ LINE _____