


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-163-01108-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks \_\_\_\_\_ County. Sec. 9 Twp. 6 Rge. 20 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines C N/2 NW NW  
Lease Owner Colorado Oil and Gas Corporation  
Lease Name STEELE Well No. 1  
Office Address P. O. Box 1030, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed \_\_\_\_\_ Jan. 1 1942  
Application for plugging filed \_\_\_\_\_ Sept. 27 1957  
Application for plugging approved \_\_\_\_\_ Sept. 27 1957  
Plugging commenced \_\_\_\_\_ Sept. 30 1957  
Plugging completed \_\_\_\_\_ Oct. 5 1957  
Reason for abandonment of well or producing formation Producing zone depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ April 31 1957  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Precambrian Sand Depth to top 3613 Bottom 3639 Total Depth of Well 3639 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 161'   | None       |
|           |         |      |    | 4-1/2" | 3602'  | 1493'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3639' and found it open. Filled with sand to 3950' and ran 4 sacks of cement. Pulled 26 jts of 4-1/2" casing. Pumped in 20 sacks of gel mud, pulled pipe to 500' and pumped in 25 sacks of cement. Pulled pipe to 150' and pumped in 20 sacks of cement. Pulled rest of 4-1/2" casing. Mudded the hole to 25', set a rock bridge and ran 5 sacks of cement to base of cellar.

RECEIVED  
OCT 19 1957  
CONSERVATION DIVISION  
Wichita, Kansas  
10-19-57

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs  
Bill K. Henrichs  
P. O. Box 1030, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 1957

My commission expires August 19, 1959  
Helen L. Martin Notary Public.

PLUGGING  
FILE SEC 9 1 6 200  
BOOK PAGE 48 LINE 43