


15-163-02386-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Rooks County. Sec. 9 Twp. 6S Rge. 20 xxx (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines A/C NW $\frac{1}{4}$ NE $\frac{1}{4}$ NW $\frac{1}{4}$
Lease Owner Barnett Oil Company
Lease Name Steele Well No. 1
Office Address 411 First Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Pipe Set December 1, 1957
Application for plugging filed January 27, 1958
Application for plugging approved January 28, 1958
Plugging commenced January 25, 1958
Plugging completed February 2, 1958
Reason for abandonment of well or producing formation Pipe Set - No Production
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3641 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3640'	2845'
				8 5/8"	178'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3641'.
Plugging started 1-25-58. Finished 2-2-58.
Plugged off bottom with sand to 3609' and dumped 4 sacks cement.
Shot 5 1/2" casing at 2,845'. Pulled pipe to 688'. Circulated mud and spotted 20 sacks cement. Pulled pipe to 160' and spotted 20 sacks cement.
Plugged well as follows: Mud to 40'. Set rock bridge and mixed 10 sacks cement. Well completed.

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1958
CONSERVATION DIVISION
Wichita, Kansas
2-21-58

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
F. H. Rousey, Office Manager, ~~(employer or owner) or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey
411 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of February, 19 58
Mildred F. Willis
Notary Public.

My commission expires February 27, 1960.

PLUGGING
FILE SEC 9 T 6 R20W
BOOK PAGE 78 LINE 31