

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Crown Energy Company

Address: One North Hudson, Sixth Floor, Oklahoma City, OK 73102-5011

Phone: (316) 321-0550 Operator License #: 33192

Type of Well: oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3/14/04 (Date)

by: Donald "Butch" Hoberecht (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Mississippi Depth to Top: 2710 Bottom: 2762 T.D. 2775

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-215-20525-00-00

Lease Name: Brainard Brainerd

Well Number: 3

Spot Location (QQQQ): SW-NE-NE-1250 Feet from North / South Section Line

660 Feet from East / West Section Line

Sec. 3 Twp. 25 S. R. 3 East West

County: Butler

Date Well Completed: na

Plugging Commenced: 2-13-04

Plugging Completed: 3-11-04

2-26-04

KCC BEN 2-15-05 RBDMS CP 7/3 KCC BEN 2-18-05 RBDMS CP 7/3

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Mississippi, Water, 2746, 2749, 8 5/8, 200', 0. Row 2: 5 1/2, 2775', 0.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bottom plug, sanded back to 2685'. Dumped 6 sx cmt on top of sand with dump bailer. Cmt top 2649'. Perforated pipe @250' with 3 holes. Ran 1" to 250' pump 110 sx cmt. Cmt top 105'. Ran 1" to 105' pump 250 sx cmt to surface.

Name of Plugging Contractor: BPC Well Plugging License #: 32475

Address: Box 282, Burden, KS 67019

Name of Party Responsible for Plugging Fees: Crown Energy Company

State of Kansas County, Butler, ss.

Dallas Flowers (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Dallas Flowers

(Address) PO Box 249, El Dorado, KS 67042

RHONDA L. MOSIMAN NOTARY PUBLIC STATE OF KANSAS MY APPT. EXPIRES 2/21/06

SUBSCRIBED and SWORN TO before me this 14 day of Feb, 2005

Rhonda Mosiman My Commission Expires: 2/21/06 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED FEB 15 2005 KCC WICHITA