

15-163-21277-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED

Form CP-4
Rev. 12-15-80

OCT 21 1982

10-21-82

WELL PLUGGING RECORD

CONSERVATION DIVISION
Wichita Kansas

Give All Information Completely
Make Required Affidavit

COUNTY ROOKS SEC. 12 TWP. 6S RGE. 20 N/W
Location as in quarters or footage from lines:
C N/2 NE SE SEC. 12

Sec 12

			GARTRELL A-3

Locate Well
correctly on above
Section Platt.

Lease Owner WILLIAM E. CARL-HAWN BROS.
Lease Name GARTRELL Well No. A-2
Office Address 5700 South Quebec, #105, ENGLEWOOD, CO 80111
Character of Well (Completed as Oil, Gas or Dry Hole): OIL
Date Well Completed 3/29/81
Application for plugging filed 10/5/82
Plugging commenced 10/13/82
Plugging completed 10/14/82
Reason for abandonment of well or producing formation _____

Noncommercial
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well CARL GOODROW
Producing formation REAGAN SAND Depth to top 3583 bottom R.T.D. 3625
Show depth and thickness of all water, oil and gas formations. PBTD 3599

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
REAGAN DST #1	255' Gas cut free oil	3577	3591	8 5/8 20# 4 1/2 10 1/2 #	331 3643	-0- 2180

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from 3599 feet
to 3500 feet for each plug set.

10 sx cement set with dump bailer off TD. Plug about 100' thick. Shot casing off at
2180' & POH. Plugged by pumping 4 sx hulls, 30 sx gel, and 100 sx 50/50 POZ with 6% gel
and 3% cc. Squeezed off with 100 sx at 1500 PSI.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PFEIFER WELL SERVICE

STATE OF COLORADO COUNTY OF ARAPAHOE, ss.
DENNIS BARRY (employee of owner) ~~XXXXXX~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Dennis Barry
5700 SOUTH QUEBEC, #105
(Address)
ENGLEWOOD, CO 80111

SUBSCRIBED AND SWORN TO before me this 19th day of OCTOBER, 19 82

Evelyn S. Roberts
EVELYN S. ROBERTS Notary Public.

My Commission expires: 16 January 1983