

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12-20-2004 (Date)
by: Darrel Dippman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Johnson Depth to Top: 4608' Bottom: 4620' T.D. _____
LKC Depth to Top: 4271' Bottom: 4274' T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-109-20, 337³⁷⁷-00-00
Lease Name: Hubert "P"
Well Number: #1
Spot Location (QQQQ): 10'W - NE - SE - NW
1650' Feet from North / South Section Line
2300' Feet from East / West Section Line
Sec. 28 Twp. 11 S. R. 33 East West
County: Logan 8/9/85
Date Well Completed: 05/16/85
Plugging Commenced: 12/23/04
Plugging Completed: 12/23/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil/Water	4062'	4341'	8.625"	326'	-0-
Johnson	Oil/ Water	4606'	4667'	4.500"	4719'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 260 sx. 60/40 pozmix cement with 10% gel & 550 # hulls down 4 1/2" csg. Les set one hour while waiting on additional cement. Pumped 10 sx 60/40 pozmix cement with 10% gel, down 4 1/2" csg. Max pressure = 600#; shut in @ 500 #. Plugging complete @ 11:45 a.m. on 12/23/04, witnessed and approved by Darrel Dippman with the KCC.

RECEIVED
FEB 16 2005
KCC WICHITA

Name of Plugging Contractor: Allied Cementing Company, Inc. License #: 99996
Address: P. O. Box 31, Russell, KS 67665
Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of _____ County, _____, ss.

Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

JENNIFER L. FOSS
Notary Public - State of Kansas
My Appt. Expires 10/14/07

(Signature) [Signature]
(Address) P. O. Box 783188

SUBSCRIBED and SWORN TO before me this 15 day of February, 20 05
[Signature] My Commission Expires: 10/14/07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202