


15-163-01093-00-00

All Information Completely  
Required Affidavit  
For Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks County. Sec. 14 Twp 6S Rge 20W (X) (W)  
Location as "NE/CNW\*SW\*" or footage from lines. SW SW NW  
Lease Owner Don E. Pratt Oil Operator  
Lease Name Simons Well No. 1  
Office Address P. O. Drawer 656, Hays, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-10-63 19  
Application for plugging filed 11-10-63 19  
Application for plugging approved 11-10-63 19  
Plugging commenced 11-10-63 19  
Plugging completed 11-10-63 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3640 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	182'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

RECEIVED  
STATE CORPORATION COMMISSION

Mud to 540' Plug & 20 sacks cement

Mud to 180' Plug & 20 sacks cement

Mud to 40' Plug & 10 sacks cement

NOV 14 1963  
11-14-63

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
P. O. Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of November, 1963

My commission expires April 1, 1967

Ulanda Nichols  
Notary Public.



DRILLER'S LOG

COMPANY: Don E. Pratt Oil Operator  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: SIMONS #1  
 LOCATION: SW SW NW Sec. 14-6S-20W  
 ROOKS COUNTY, KANSAS  
 COMMENCED: 11-2-63  
 COMPLETED: 11-9-63

0	70	Shale
70	105	Sand & Gravel
105	182	Shale
182	660	Shale & Shells
660	1520	Shale, Sand, Redbed
1520	1745	Red Shale
1745	1778	Anhydrite
1778	2235	Shale
2235	3005	Shale & Lime
3005	3105	Lime
3105	3250	Shale & Lime
3250	3613	Lime
3613	3640	Chert
	<u>3640</u>	<u>Rotary Total Depth - D. &amp; A.</u>

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 NOV 14 1963  
 11-14-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" new Surface Casing @ 182' Cemented with 150 sacks HA5.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Simons #1 well, located SW SW NW of Section 14, Township 6 South, Range 20 West, Rooks County, Kansas, as reflected by the files of Leben Drilling, Inc.

*Leslie Kite*

Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 12th day of November, 1963.

*Ulanda Nichols*

Ulanda Nichols, Notary Public

My Commission Expires:  
 April 1, 1967